ENGINEERING DEPARTMENT.

OFFICE OF THE EXECUTIVE ENGINEER, No. IV, TUNNEL DIVISION, HULIKERE.

Notification.

It is hereby notified for the information of the public, that the following old rails released from works are available for sale at the Tunnel Works, Hulikere Post, Bydarahalli Railway Station, Mysore Railways.

Intending purchasers may apply with their offers to the Executive Engineer, No. IV, Tunnel Division, Hulikere, after inspecting the articles, if necessary. In the case of offers accepted, the articles will be delivered on payment *in cash of the full amount of the sale.*

Sl. No.	Items	Quantity available	Remarks
		R.ft.	
1	Old M. S. M. Rails 41¼ lbs. per yard ...	47,596	Released from Works and serviceable.
2	Old Rails 18 lbs. per yard	3,043	Do

B. KRISHNASWAMI IYENGAR,
Executive Engineer.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Notification dated 4th May 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore, up to 2 P.M. on 30*th May* 1932 for *constructing* (1) *two Blocks of Operators' Quarters and* (2) *two blocks of Cooly Quarters at Dodballapur.*

1. The tenders will be opened in public at 2 P.M. on 30*th* May 1932. The work should be completed within *five months* and the monthly progress should not be less than *Rs.* 2,500.

2. The plan, detailed estimates and the conditions may be seen at the Office of the Chief Electrical Engineer, Bangalore, on all working days during the office working hours.

3. The tenders should be accompanied by a statement in the form attached showing the rates at which different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of *Rs.* 500 in cash or Government promissory notes, as earnest money and be superscribed "Tenders for Constructing Residential Buildings at Dodballapur," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any reasons whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender the successful tenderer will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the notice board of the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a week from the date of notification of acceptance.

10. Water for construction should be got at the contractor's own expense.

11. Specifications for works are those recognised by the Mysore Public Works Department and Marryot's specifications.

12. The contractor should be bound by the conditions of the Schedule of Contract of the Electrical Department.

Statement showing approximate quantities of work for Constructing one unit of Operators' Quarters for accommodating two families and one Block of Latrine at Dodballapur.

Sl. No.	Description of items	Unit	Quantity in	
			Operators' quarters	Latrine
1	Earthwork excavation and filling in basement ...	C.yd.	51	4
2a	Stone jelly in ordinary mortar concrete foundation ...	C.ft.	577	...
b	Stone in clay foundation and basement including through stones fixed at 6'—0" centre to centre in every course.	,,	1055	136
c	Burnt brick in clay superstructure	,,	2108	...
d	Do in mortar do	,,	440	196
e	Stone slabs 6" thick roughly dressed and set in mortar	S.ft.	237	...
f	Do 4" thick set in lime mortar	,,	24	...
g	Chunam plastering 2 coats	Square	56·36	4·91
h	Chunam pointing with thread lines	,,	2·10	0·56
i	White and colur washing 2 coats	,,	58·46	5·47
j	Binding wall 1·½' x 9" brick in mortar and chunam plastered complete.	R.ft.	44	...
k	Plain cornice 6" projection brick in mortar and chunam plastered complete.	,,	44	...
l	Constructing sinks complete...	Each	2	...
m	Providing stone, mortar and pestle including fixing ...	,,	2	...
3	Flooring with 3" concrete with a coat of cement well trowelled over smooth and even.	Square	8·79	...
4a	Roofing with 1st class Mangalore tiles on T. W. reepers 2" x 1" including wood oiling to reepers.	,,	10·72	...
b	Ridge tiles set in mortar and cement pointed ...	R.ft.	41	...
c	Roofing with Cudappa slabs 1½" with 3" brick concrete and 2 layers of flat tiles and surface plastered and ceiling cement pointed and white washed.	Square	320	...
d	Burnt brick in mortar cornice projection 9" complete	R.ft.	63	...
e	Burnt brick in mortar parapet wall 9" thick as per design in drawing.	,,	59	...
f	Ventilating tiles...	Each	8	...
5a	Mattywood wrought and put up with 2 coats of wood oiling.	C.ft.	34·17	...
b	Steel girders fixed complete. (Tatas make) ...	Cwt.	19·13	...
c	Doors with T.W. frames with H.W. battened shutters 1" thick with fittings, etc.. complete.	S.ft.	279·5	...
d	Windows with T.W. frames and H.W. battened shutters 1" thick with iron bars 5/8" dia. with all accessory fittings, etc., complete.	,,	116	...
e	H.W. planks 1¼" thick for shelves with T.W. pegs fixed complete.	,,	48	...
f	Chocolate painting 2 coats	Square	13·76	...
g	Expanded metal 3" x 1½" x ⅛" with t.w. frames fixed complete including doorway.	S.ft.	116	...
6	Rain water down pipe 3" dia. fixed complete ...	R.ft.	25	...
7	Brick in mortar pillar 1·1/8' square with base and capital complete with chunam plaster 7'—7" high.	Each	1	...
8	Galvanized sheet sun shades on T.W. battens painted with chocolate 2 coats.	,,	6	...
9	Electric lighting and water supply	1 item	Departmental.	..
10	Cement plastering ½" thick	Square	...	0·79
11	Tar washing 2 coats	,,	...	0·63
12	Flooring with 3" concrete and cement plaster ½" thick	,,	...	0·35
13	Fixing outlets and constructing drains, etc. ...	1 item	...	L. S.
14	Providing galvanised iron sheet tubs 12" x 6" with handles, etc., complete with tarring.	Each	..	6

Statement showing the approximate quantities of work for constructing one Block of Cooly Sheds with a Block of Latrine at Dodballapur.—

Sl. No.	Description of item	Unit	Quantity in	
			Cooly shed.	Latrine
1	Earthwork excavation including filling in basement ..	C.yd.	44	4
2a	Concrete stone jelly in ordinary mortar ...	C.ft.	347	...
b	Coursed rubble stone masonry in clay foundation and basement including through stones at 6 ft. intervals in every course.	,,	986	130
c	Burnt brick in clay superstructure ...	,,	2,070	...
d	do in mortar do ...	,,	352	196
e	Stone slabs 4" thick roughly dressed and fixed in mortar.	S.ft.	156	..
f	Stone pillars 4" thick including paly cutting and fixed in position.	,,	26	...
g	Plain cornice 6" projection built of brick in mortar and chunam plastered complete.	R.ft.	75	..
h	Chunam plastering two coats ...	Sqr.	52·16	4·91
i	Pointing with chunam mortar including thread lines	,,	1·00	0·56
j	White and colour washing two coats ...	,,	53·16	5·47
k	Binding wall 1·1/8' x 3/4' brick in mortar and chunam plastered and whitewashed.	R.ft.	74	...
1	Chunam borders 6" x 3" over verandah roof ...	,,	30	....
3	Flooring with 3" concrete and a coat of cement plaster well trowelled and finished smooth and even.	Sqr.	8·20	...
4a	Roofing with First Class Mangalore tiles on teak reepers including wood oiling to reepers.	,,	11·81	...
b	Ridge tiles set in mortar and cement pointed ...	R.ft.	23	...
c	Ventilating tiles set in mortar ...	Each	16	...
d	Mattywood work with oiling two coats ..	C.ft.	41·50	...
e	Doors teakwood frames with honeywood battened 1¼" thick shutters with fitting, etc., complete.	S.ft.	78	..
f	Windows with teakwood frames and honnewood battened shutters 1" thick with iron bars 5/8" dia. and necessary fittings, etc., complete frames to be of 4" x 3".	,,	70	..
g	Ventilators with teakwood and glazed shutters fixed complete (frames to be of 3" x 3"),	,,	24	...
h	Chocolate painting two coats ...	Sqr.	3·55	..
i	Constructing sinks with drain pipes complete ...	Each	4	...
j	Providing stone, mortar and pestle including fixing ...	,,	4	...
k	Galvanized iron sheet sun shades on teakwood battens with chocolate painting.	,,	4	...
5	Flooring with 3" concrete bed with cement plastering ½" thick on top.	Sqr.	..	0·38
6	Cement plastering ½" thick ...	,,	...	0·79
7	Tar washing two coats ...	,,	....	0·63
8	Fixing outlets from the latrine with drains complete	1 item	Lump sum	
9	Providing galvanized iron sheet tubs 12"x 6" with handles, etc.. complete with tarring.	Each	...	6

V. R. COWSICK,
For *Chief Electrical Engineer to the Government of Mysore.*

KADUR DIVISION.

Abstract Notification.

The attention of the public is invited to the detailed Notification calling for tenders for restoring Kalasapur Naikankere, published on pages 431 to 433 of Part VI of *Mysore Gazette* of 5th May 1932. The last date for receiving tender is 23rd May 1932 till 3 P.M.

L. A. H. WINCKLER,
Executive Engineer.